


INSPECTION

1. INSPECT A/C INDICATOR OPERATION

- (a) Connect the positive (+) lead from the battery to terminal 6 and the negative (–) lead to terminal 4.
- (b) Push the A/C button in and then check that the indicator lights up.


If operation is not as specified, replace the switch.



2. INSPECT DIMMING OPERATION

- (a) Connect positive (+) lead from the battery to terminal 6 and negative (–) lead to terminal 4 and 1.
- (b) Connect the positive (+) lead from the battery to terminal 3 and then check that the indicator dims.

If operation is not as specified, replace the switch.



3. INSPECT A/C SWITCH CONTINUITY

Condition/Circuit	Tester connection	Specified condition
OFF	–	No continuity
ON	5 – 6	Continuity
Illumination circuit	3 – 1	Continuity

If operation is not as specified, replace the switch or test the bulb.