


AIR CONDITIONING CONTROL ASSEMBLY (Center Cluster Integration)

ON-VEHICLE INSPECTION

AC350-02


1. REMOVE CENTER CLUSTER INTEGRATION PANEL
(See page AC-89)
2. Access cab, Standard cab:
INSPECT A/C CONTROL ASSEMBLY CIRCUIT
 - (a) Disconnect the connectors from the A/C control assembly and inspect the connectors on the wire harness side, as shown in the chart below.
Test condition:
Turn the ignition switch to ON

Wire harness side



Connector "A"

I11149
I11150




Connector "B"

I11198

Tester connection	Condition	Specified condition
A1 – Ground	Constant	Continuity
A4 – Ground	Turn ignition switch to ON	Battery positive voltage
	Turn ignition switch OFF	No voltage
A5 – Ground	Constant	Battery positive voltage
A13 – Ground	Turn ignition switch to ACC	Battery positive voltage
	Turn ignition switch OFF	No voltage
B11 – Ground (5VZ-FE engine)	Constant	Continuity
B20 – B10	Evaporator temperature at 25°C (77°F)	1.5 kΩ

If the result is as specified, replace the amplifier with a new one.
If the result is not as specified, inspect the circuits connected to other parts.

- (b) Connect the connectors to the A/C control assembly and inspect the connectors on the wire harness side from the back side, as shown in the chart below.
- Test condition:
- Run the engine at idle speed
 - Set the manifold gauge set



Tester connection	Condition	Specified condition
B1 – Ground	Constant	Continuity
B8 – Ground	Magnetic clutch is engaged	Battery positive voltage
	Magnetic clutch is not engaged	Below 1.0 V
B13 – Ground	Air inlet switch "FRESH"	Below 1.0 V
	Air inlet switch "RECIRC"	Battery positive voltage
B15 – Ground	Air inlet switch "RECIRC"	Below 1.0 V
	Air inlet switch "FRESH"	Battery positive voltage
B19 – Ground	A/C switch ON	Below 1.0 V
	A/C switch OFF	Battery positive voltage


If the result is as specified, replace the amplifier with a new one.
If the result is not as specified, inspect the circuits connected to other parts.

3. Double cab:
INSPECT A/C CONTROL ASSEMBLY CIRCUIT

- (a) Disconnect the connectors from the A/C control assembly and inspect the connectors on the wire harness side, as shown in the chart below.

Test condition:

Turn the ignition switch to ON




Tester connection	Condition	Specified condition
A10 – Ground	Constant	Continuity
A14 – Ground	Turn ignition switch ON	Battery positive voltage
	Turn ignition switch OFF	No voltage
A15 – Ground	Constant	Battery positive voltage
A9 – Ground	Turn ignition switch to ACC	Battery positive voltage
	Turn ignition switch OFF	No voltage

If the result is as specified, replace the amplifier with a new one.
If the result is not as specified, inspect the circuits connected to other parts.

- (b) Connect the connectors to the A/C control assembly and inspect the connectors on the wire harness side from the back side, as shown in the chart below.

Test condition:

- Run the engine at idle speed
- Set the manifold gauge set



Tester connection	Condition	Specified condition
A10 – Ground	Constant	Continuity
A18 – Ground	Magnetic clutch is engaged	Battery positive voltage
	Magnetic clutch is not engaged	Below 1.0 V
B8 – Ground	Air inlet switch "FRESH"	Battery positive voltage
	Air inlet switch "RECIRC"	Below 1.0 V
B7 – Ground	Air inlet switch "RECIRC"	Battery positive voltage
	Air inlet switch "FRESH"	Below 1.0 V
B12 – Ground	A/C switch ON	9.0 V
	A/C switch OFF	Below 1.0 V

If the result is as specified, replace the amplifier with a new one.
If the result is not as specified, inspect the circuits connected to other parts.